

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work : Improvements to Roads and Drains at Byarappa Garden, KNE College 4th Block, Kateramma Layout cross Roads in ward No 10 Doddabommasandra

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	17.60	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 & M-20. MORTH with all lead and left as per directions of engineer in charge of the work.	Cum	496.00	Rupees Four Hundred Ninety Six Only
2	1282.73	KSRRB 300-3. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil involving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification with all lead and left as per directions of engineer in charge of the work.	Cum	220.40	Rupees Two Hundred Twenty and Forty Paise Only
3	192.96	Removing And Refixing stone slabs of drains and pointing in C.M (1:3) with all lead and left as per directions of engineer in charge of the work.	Sqm	111.30	Rupees One Hundred Eleven and Thirty Paise Only
4	438.65	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. with all lead and left as per directions of engineer in charge of the work.	Cum	5509.33	Rupees Five Thousand Five Hundred Nine and Thirty Three Paise Only
5	83.05	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications do- Wall & bottom thickness 15cm with all lead and left as per directions of engineer in charge of the work.	Cum	7189.42	Rupees Seven Thousand One Hundred Eighty Nine and Forty Two Paise Only
6	5.48	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. with all lead and left as per directions of engineer in charge of the work.	Tonne	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six and Ninety Eight Paise Only

222.84	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surface on both sides etc, and complete as per the directions of Engineer in charge. (with all lead and left as per directions of engineer in charge of the work.	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
8 63.90	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum, with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008, Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and pointing for joints 1:3 cement mortar including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per the directions of Engineer in-Charge. with all lead and left as per directions of engineer in charge of the work.	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
9 354.18	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials separately complete as per specifications. with all lead and left as per directions of engineer in charge of the work.	Cum	952.94	Rupees Nine Hundred Fifty Two and Ninety Four Paise Only
10 2729.77	KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, HOM of machinery complete as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	6.36	Rupees Six and Thirty Six Paise Only
11 409.47	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. with all lead and left as per directions of engineer in charge of the work.	Cum	2001.28	Rupees Two Thousand One and Twenty Eight Paise Only


E.E. (BTR DIV)

Cement concrete pavement. Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregates , with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design. laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum) with all lead and left as per directions of engineer in charge of the work.

12 476.30

Cum 5354.02

Rupees Five
Thousand Three
Hundred Fifty Four
and Two Paise Only

Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift with all lead and left as per directions of engineer in charge of the work.

13 3213.81

Sqm 72.08

Rupees Seventy Two
and Eight Paise Only


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

